

राष्ट्रीय आयुर्वेद संस्थान
मानद विश्वविद्यालय (डी-नोवो), जयपुर

क्रमांक एफ. 4(64)/सम्पदा/2022/12642

दिनांक : 09/11/22

अल्पकालीन निविदा

संस्थान स्वामी लक्ष्मीराम छात्रावास की सिढियों पर बंदरों से सुरक्षा हेतु लौहे की जाली लगाने का कार्य करवाया जाना है। जो निम्नलिखित विवरण अनुसार निविदाओं के माध्यम से कार्य करवाया जाना है इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएँ दिनांक 16.11.2022 को सांय 4:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करे। कार्य का विवरण निम्नप्रकार है :-

S.N	Description	Qty.	Rate per unit	Amount
1.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :	136 Sqm.		
2.	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	30 Sqm.		
3.	Providing and fixing hard drawn steel wire fabric of size 75 x25 mm mesh (Material supply by department))	136.50		
4.	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position (Material supply by department)) In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	1846 kg.		
5.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete			
	Hot finished welded type tubes	465 Kg.		

- उक्त कार्य का भुगतान सन्तोषप्रद होने पर किया जायेगा।
- उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
- फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
- फर्म द्वारा कोटेशन में GST का उल्लेख करना अनिवार्य है अन्यथा प्राप्त कोटेशन में प्रस्तुत दर को GST सहित माना जावेगा।
- कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

संयुक्त निदेशक (प्रशासन)